



# How to Verify Key Components of Heating & AC Systems in ENERGY STAR Certified Homes

February 28, 2013  
RESNET Conference

Rick Gazica, ICF International; Brett Dillon, IBS Advisors, LLC

Learn more at [energystar.gov](http://energystar.gov)

# Agenda

---



- Value of quality-installed heating & cooling systems.
- Overview of Sections 1-4 of the HVAC System QI Rater Checklist.
- Critical details of Sections 1-4.
- Q&A.



---

# **Value of Quality-Installed Heating & Cooling Systems**

# Heating & cooling systems



2


## Heating, Cooling, & Ventilation System

- Heating and cooling equipment that is:
  - High efficiency
  - Properly designed and installed
  - Combined with a duct system that's insulated, sealed, and balanced
- ... maintains comfort with less energy.

# Heating & cooling systems



- Adding & removing Btu's impacts the temp. inside the home.



# Heating & cooling systems




- You can't have a complete HVAC system until you first have a complete thermal enclosure system.
- The amount of heat transfer can be quantified in British Thermal Units (Btu's).
- 1 Btu is approximately equal to the energy in a single match.



# Heating & cooling systems



- Adding & removing Btu's impacts the temp. inside the home.



# Three major steps to design an HVAC system



1) Calculate the heating & cooling load.



2) Select equipment to meet those loads.




3) Design ducts to get air from equipment to rooms, and then back to equipment, to offset loads.



# Step 1: Calculate heating & cooling loads




- Cooling load is the maximum Btu's added in one hour.



# Step 1: Calculate heating & cooling loads




- Heating load is the maximum Btu's lost in one hour.



## Step 2: Select equipment that meets loads




- Select equipment that removes Btu's to meet cooling load.



## Step 2: Select equipment that meets loads




- Select equipment which adds Btu's to meet heating load.



## Step 3: Design the duct system



- Design ducts to properly distribute air through house. This offsets the loads.



# Value of quality-installed Heating & cooling systems



- Two components of a complete system:

Proper design



Proper installation





# Overview of Sections 1-4 of the Checklist

# Section 1: Review of HVAC System QI Contractor Checklist

---




- 1) Collect design documentation for record-keeping.
- 2) Review design parameters to see if they match rated home.
- 3) Visually verify that equipment matches what was specified.
- 4) Check data from HVAC contractor's commissioning process.
- 5) Check if contractor holds required credentials.




## Item 1.2.5: Window area



- Window area is within  $\pm 10\%$  of calculated window area of rated home.



Design



Actual



## Section 2: Duct quality installation

---



- Visual inspection of duct installation.
- Review of quantity and location of duct terminations.
- Bedroom pressure balancing.

## Section 3 & 4: Duct insulation & leakage

---



- Minimum insulation values for ductwork in unconditioned space.
- Maximum allowable total duct leakage levels and to outdoors.

# Section 1 through 4: Summary

---



- Oversight of key features of the design process.
- Inspection of duct installation quality.
- Verification of duct insulation and leakage levels.





---

# **Critical Details of the HVAC System QI Rater Checklist**

# Item 1.1: Collection of required documentation



- Required documentation includes Checklist, ventilation system design, load calculations, & AHRI certificate.

**ENERGY STAR Qualified Homes, Version 3  
HVAC System Quality Installation Contractor**

Home Address: 1523 Woodrow Ave City: Baltimore  
System Description: Air-Condition Furnace Cooling system for temporary occupant load\*

**1. Whole-Building Mechanical Ventilation Design**

1.1 Ventilation system installed that has been designed to meet ASHRAE 62.2-2010 requirements including, but not limited to, requirements in Items 1.2-1.5.  
1.2 Ventilation system does not utilize an intake duct to the return side of the HVAC system unless the system is designed to operate intermittently and automatically based on a timer and to restrict outdoor air intake when not in use (e.g., motorized damper).  
1.3 Documentation is attached with ventilation system type, location, design rate, and frequency and duration of each ventilation cycle.  
1.4 If present, continuously-operating vent & exhaust fans designed to operate during all occupiable hours.  
1.5 If present, intermittently-operating whole-house ventilation system designed to automatically operate at least once per day and at least 10% of every 24 hours.

**2. Heating & Cooling System Design**

2.1 Heat Loss / Gain Method:  Manual J v8  2009 ASHRAE  Other: \_\_\_\_\_  
2.2 Duct Design Method:  Manual D  Other: \_\_\_\_\_  
2.3 Equipment Selection Method:  Manual S  OEM Rec.  Other: \_\_\_\_\_  
2.4 Outdoor Design Temperatures: \* Location: Baltimore 1%: 25 °F 99%: 32 °F  
2.5 Orientation of Rated Home (e.g., North, South): South  
2.6 Number of Occupants Served by System: 18  
2.7 Conditioned Floor Area in Rated Home: 3200 Sq. Ft.  
2.8 Window Area in Rated Home: 450 Sq. Ft.  
2.9 Predominant Window SHGC in Rated Home: 11  
2.10 Infiltration Rate in Rated Home: 11 Summer: 3ACH Winter: 3ACH  
2.11 Mechanical Ventilation Rate in Rated Home: 30 CFM  
2.12 Design Latent Heat Gain: 3000 BTUH  
2.13 Design Sensible Heat Gain: 3000 BTUH  
2.14 Design Total Heat Gain: 3400 BTUH  
2.15 Design Total Heat Loss: 3100 BTUH  
2.16 Design Airflow: 2000 CFM  
2.17 Design Duct Static Pressure: .8 In. Water Column  
2.18 Full Load Calculations Report Attached 11

**3. Selected Cooling Equipment, if Cooling Equipment to be Installed**

3.1 Cooler Manufacturer's Model: JAC624804  
3.2 Evaporator / Fan Coil Manufacturer & Model: JAC624804  
3.3 AHRI Reference #: 478313  
3.4 Listed Efficiency: 11.0 EER 16.0 SEER  
3.5 Metering Device Type:  TXV  Fixed orifice  Other: \_\_\_\_\_  
3.6 Refrigerant Type:  R-410a  Other: \_\_\_\_\_  
3.7 Fan Speed Type:  Fixed  Variable (ECM / ICM)  Other: \_\_\_\_\_  
3.8 Listed Sys. Latent Capacity at Design Cond.: 3000 BTUH  
3.9 Listed Sys. Sensible Capacity at Design Cond.: 3100 BTUH  
3.10 Listed Sys. Total Capacity at Design Cond.: 3400 BTUH  
3.11 H-Listed Sys. Latent Capacity (Value 3.8) ÷ Design Latent Heat Gain (Value 2.12), ENERGY STAR qualified dehumidifier installed  
3.12 Listed Sys. Total Capacity (Value 3.10) ÷ 95-115% of Design Total Heat Gain (Value 2.14) or next nominal size 11  
3.13 AHRI Certificate Attached 11

**4. Selected Heat Pump Equipment, if Heatpump to be Installed**

4.1 AHRI Listed Efficiency: \_\_\_\_\_ HSPF  
4.2 Performance at 17°F: Capacity \_\_\_\_\_ BTUH Efficiency: \_\_\_\_\_ COP  
4.3 Performance at 47°F: Capacity \_\_\_\_\_ BTUH Efficiency: \_\_\_\_\_ COP

Effective for homes permitted starting 11/10/2012 Revised 9/10/2012

**Rhvac - Residential & Light Commercial HVAC Loads**

ICF International  
Arlington, VA, 22209

**Project Report**

**General Project Information**  
Project Title: RESNET - Houston - EBv3  
Designed By: Michael Brown  
Project Date: Wednesday, October 31, 2012

**Design Data**  
Reference City: Houston, Texas  
Building Orientation: Front door faces North  
Daily Temperature Range: Medium  
Latitude: 29 Degrees  
Elevation: 96 ft  
Altitude Factor: 0.997

	Outdoor Dry Bulb	Outdoor Wet Bulb	Outdoor Rel Hum	Indoor Rel Hum	Indoor Dry Bulb	Grains Difference
Writer:	32	29.92	80%	n/a	70	n/a
Summer:	94	77	47%	50%	75	48

**Check Figures**  
Total Building Supply CFM: 856 CFM Per Square Ft.:  
Square Ft. of Room Area: 2,400 Square Ft. Per Ton:  
Volume (ft³) of Cond. Space: 19,200

**Building Loads**  
Total Heating Required Including Ventilation Air: 28,773 Btuh 28,773 MBH  
Total Sensible Gain: 18,786 Btuh 84 %  
Total Latent Gain: 3,452 Btuh 16 %  
Total Cooling Required Including Ventilation Air: 22,218 Btuh 1.85 Tons (Based On

**Notes**  
Rhvac is an ACCA approved Manual J and Manual D computer program. Calculations are performed per ACCA Manual J 8th Edition, Version 2, and ACCA Manual D. All computed results are estimates as building use and weather may vary. Be sure to select a unit that meets both sensible and latent loads according to the manufacturer's performance design conditions.

**AHRI CERTIFIED**  
www.ahridirectory.org

This furnace qualifies for AFUE & AMACF Federal Energy Efficiency Tax Credit when placed in service between February 17 2009 and December 31 2011.

**Certificate of Product Ratings**

AHRI Certified Reference Number: 4705242 Date: 1/19/2012

Product: Residential Furnace Heating Equipment  
Model Number: G5MV1060174A  
Manufacturer: INTERNATIONAL COMFORT PRODUCTS, LLC (USA)  
Trade/Brand name: HEIL, COMFORTMAKER, DAY & NIGHT, AIRQUEST, KENMORE, KEEPRITE, ICP COMMERCIAL

Rated as follows in accordance with Department of Energy (DOE) furnace test procedures as published in the latest edition of the Code of Federal Regulations, 10 CFR Part 430 and subject to verification of rating accuracy by AHRI-sponsored, independent, third party testing:

AFUE: 96.0%  
Output Heating Capacity: 58 MBTUH

The following data is for reference only and is not certified by AHRI:

Input: 60 MBTUH  
E1: 48.6 MMBTU/yr  
Eac: 194 kWh/yr  
PE: 37 Watts  
Furnace Type: Non-Weatherized  
Config: Upflow, Downflow, Horizontal  
Fuel Type: Natural Gas, Propane Gas

**Advanced Main Air Circulating Fan**  
\* Electrically Efficient Furnace  
Postnote 79 - This furnace is equipped with an Electronically Commutated Motor (ECM)  
Postnote 162 - May be installed as a direct vent or non-direct vent.  
Postnote 162 - Nihil character may be (A, C, H, N, or X).  
Postnote 209 - D may be replaced by S in title element design.  
Postnote 232 - Based on 12.0% Carbon Dioxide and -0.02 Bt. Water Draft.  
\* Models with an "A" label status are those that are currently in production. Models with a "S" label status are those that the manufacturer has elected to stop producing, yet stock is still available. Models with an "O" label status are those that the manufacturer is required to stop manufacturing due to an AHRI certificate program test failure.  
\* Ratings followed by an asterisk (\*) indicate a voluntary rating of previously published data, unless accompanied with a WMS, which indicates an inventory rating.

**DISCLAIMER**  
AHRI does not endorse the product(s) listed on this Certificate and makes no representations, warranties or guarantees as to, and assumes no responsibility for, the product(s) listed on this Certificate. AHRI expressly disclaims all liability for damages of any kind arising out of the use or performance of the product(s), or the unauthorized alteration of data listed on this Certificate. Certified ratings are valid only for models and configurations listed in the directory at www.ahridirectory.org.

**TERMS AND CONDITIONS**  
This Certificate and its contents are proprietary products of AHRI. This Certificate shall only be used for individual, personal and confidential reference purposes. The contents of this Certificate may not, in whole or in part, be reproduced, copied, disseminated, stored into a computer database, or otherwise utilized, in any form or manner or by any means, except for the user's individual, personal and confidential reference.

**CERTIFICATE VERIFICATION**  
The information for the model cited on this certificate can be verified at www.ahridirectory.org. click on "Verify Certificate" link and enter the AHRI Certified Reference Number and the data on which the certificate was issued, which is listed above, and the Certificate No., which is listed below.

©2012 Air-Conditioning, Heating, and Refrigeration Institute  
CERTIFICATE NO.: 129714683380960557

# Item 1.2: Review of contractor checklist & equipment




ENERGY STAR Qualified Homes, Version 3 (Rev. 06) HVAC System Quality Installation Rater Checklist <sup>1</sup>			
Home Address: _____	City: _____	State: _____	
1. Review of HVAC System Quality Installation Contractor Checklist <sup>2</sup>	Must Correct	Rater Verified	N/A
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation for ventilation system (4.2), full load calculations (2.10), and AHRI certificate (2.12)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<b>1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist Item # indicated in parenthesis).<sup>3</sup></b>			
1.2.1 Outdoor design temperatures (2.4) are equal to the 1% and 99% ACCA Manual J design temperatures for contractor-designated design location <sup>4</sup>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.2 Home orientation (2.5) matches orientation of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.3 Number of occupants (2.6) equals number of occupants in rated home <sup>5</sup>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.4 Conditioned floor area (2.7) is within ±10% of conditioned floor area of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.5 Window area (2.8) is within ±10% of calculated window area of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.6 Predominant window SHGC (2.9) is within 0.1 of predominant value in rated home <sup>6</sup>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.7 Listed latent cooling capacity (3.8) exceeds design latent heat gain (2.12)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.8 Listed sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.9 Listed total cooling capacity (3.10) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size <sup>7</sup>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.2, 5.1), and AHRI certificate or OEM catalog data all match <sup>8</sup>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temperature (as determined using pressure / temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.5) saturation temperature (± 3 degrees) <sup>9</sup>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.12 Calculated subcooling (7.1 minus 6.4) value is within ±3 °F of the reported target temperature (7.3) or calculated superheat (6.6 minus 7.5) value is within ±5 °F of the reported target temperature (7.7). <sup>9</sup>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3 Rater-verified supply & return duct static pressure ≤ 110% of contractor values (8.3, 8.4)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4 Contractor-prepared balancing report indicating the room name and design airflow for each supply and return register collected by Rater for records. In addition, final individual room airflows measured and documented on balancing report through one of the following options:			
1.4.1 Measured and documented by contractor (10.1.1), OR,	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.2 Measured by Rater using Section 804.2 of the Mortgage Industry National HERS Standard, documented by Rater, & verified by Rater to be within the greater of ± 20% or 25 CFM of design airflow (10.1.2)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5 HVAC contractor holds credentials necessary to complete the HVAC System QI Contractor Checklist <sup>10</sup>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

# Item 1.2.1: Review of contractor checklist



- Verify outdoor design temperatures equal 1% and 99% ACCA Manual J design temperatures for selected location.
- These design temperatures are available on EPA's website:  
[http://www.energystar.gov/ia/partners/bldrs\\_lenders\\_raters/downloads/Outdoor Design Conditions 508.pdf?7cdb-8623](http://www.energystar.gov/ia/partners/bldrs_lenders_raters/downloads/Outdoor_Design_Conditions_508.pdf?7cdb-8623)



Location	Dry Bulb Design Temperature	
	Winter / Heating / 99%	Summer / Cooling / 1%
Richmond, VA	18 F	92 F



# Item 1.2.2 through 1.2.6: Review of contractor checklist



- Verify that the following parameters used in the load calculation match the rated home:
  - Home orientation
  - Number of occupants
  - Conditioned floor area ( $\pm 10\%$ )
  - Window area ( $\pm 10\%$ )
  - SHGC ( $\pm 0.1$  SHGC value)
- Use the tolerances provided to make compliance easier.

## Example of Acceptable Floor Area

-10%	Design	+ 10%
1,980	2,200	2,420

# Item 1.2.2 through 1.2.6: Review of contractor checklist



2.4 Outdoor Design Temperatures: <sup>9</sup> Location: <u>Baltimore</u> 1%: <u>25</u> °F 99%: <u>93</u> °F	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.5 Orientation of Rated Home (e.g., North, South): <u>North</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.6 Number of Occupants Served by System: <sup>10</sup> <u>5</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.7 Conditioned Floor Area in Rated Home: <u>3200</u> Sq. Ft.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.8 Window Area in Rated Home: <u>450</u> Sq. Ft.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.9 Predominant Window SHGC in Rated Home: <sup>11</sup> <u>.20</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.10 Infiltration Rate in Rated Home: <sup>12</sup> Summer: <u>.3 ACH</u> Winter: <u>.3 ACH</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.11 Mechanical Ventilation Rate in Rated Home: <u>90</u> CFM	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.12 Design Latent Heat Gain: <u>9600</u> BTU/h	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.13 Design Sensible Heat Gain: <u>38400</u> BTU/h	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.14 Design Total Heat Gain: <u>48000</u> BTU/h	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.15 Design Total Heat Loss: <u>31000</u> BTU/h	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.16 Design Airflow: <sup>13</sup> <u>1600</u> CFM	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.17 Design Duct Static Pressure: <sup>14</sup> <u>.6</u> In. Water Column	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2.18 Full Load Calculations Report Attached <sup>15</sup>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>3. Selected Cooling Equipment, If Cooling Equipment to be Installed</b>		
3.1 Condenser Manufacturer & Model: <u>Carrier</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3.2 Evaporator / Fan Coil Manufacturer & Model: <u>34ChX4i014</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3.3 AHRI Reference #: <sup>16</sup> <u>879313</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3.4 Listed Efficiency: <u>13</u> EER <u>16</u> SEER	<input checked="" type="checkbox"/>	<input type="checkbox"/>

## Item 1.2.10: Checking installed equipment




- HVAC manufacturer & model numbers on installed equipment, Contractor Checklist, & AHRI certificate match.

Equipment selected  
during design:



Model ABC

Equipment actually  
installed in home:



Model 123


## Item 1.2.11 & 1.2.12: Review of contractor checklist

---



- The Rater completes two simple math calculations to help ensure that the equipment has the right amount of refrigerant.
- Even though these Items just require some simple math, it helps to understand the concepts behind them.

# Refrigerant Tests & Calculations




# Refrigerant Tests & Calculations



## Step 1: Metering Device

- The metering device controls how much refrigerant is released to the evaporator inside the home




# Refrigerant Tests & Calculations



## Step 2: Evaporator

- The refrigerant flows through the evaporator or cooling coil in the air handler unit, transferring heat between the air and the refrigerant




# Refrigerant Tests & Calculations



## Step 3: Compressor

- The compressor is a small mechanical device that compresses the gas, raising its temperature






# Refrigerant Tests & Calculations



## Step 4: Condenser

- The condenser uses a fan to blow outdoor air across the refrigerant, removing heat, causing it to cool down and condense back into a liquid form



# Refrigerant Tests & Calculations

Why is the amount of refrigerant so important to the operation of the A/C unit?

- Keep temperatures within target ranges
- Keep liquid out of gas side

Consequences of improper charging:

- Inefficient operation
- Premature compressor failures



# Item 1.2.11 & 1.2.12: Review of contractor checklist



- Two tests can be done to ensure proper amount of refrigerant:
  - Subcooling test:  
Ensures the refrigerant is in liquid form after it leaves the condenser.
  - Superheat test:  
Ensures the refrigerant is in gas form before it arrives at the compressor.


A photograph of a refrigerant label on a metal surface. The label contains technical specifications for a compressor. A red rectangular box highlights the "INDOOR TXV SUB COOLING" value, which is 11 °F.

SERIAL	2410E19709		
PROD	25HPA536A0031010		
MODEL	25HPA536A310		
METERING DEVICE	TXV	57	PISTON
INDOOR			OUTDOOR
FACTORY CHARGED	R410A		
	14.63 LBS		6.64 KG
INDOOR TXV SUB COOLING		11	°F
POWER SUPPLY	208/230	VOLTS AC	
	1	PH	60 HZ
PERMISSIBLE VOLTAGE AT UNIT	253	MAX	197 MIN
SUITABLE FOR OUTDOOR USE			
COMPRESSOR	208/230	VOLTS AC	
	1	PH	60 HZ
	17.9	HLA	79.8 LRA

# Item 1.2.11 & 1.2.12: Review of contractor checklist




- Subcooling is the temperature of a fluid below its boiling point (liquid saturation temperature).



# Item 1.2.11 & 1.2.12: Review of contractor checklist



- Superheat is the temperature of a fluid above its boiling point (liquid saturation temperature).





# Item 1.2.11: Review of contractor checklist

- Verify that difference between Rater-verified and contractor-reported saturation temperature is  $\leq 3^{\circ}\text{F}$ .
- A pressure – temperature chart shows the saturation temperature of a specific liquid at a variety of pressures.

Temp. (F)	R410A (psig)
35	107
40	118
45	130
50	142
55	155
60	170
65	185
70	201
75	217
80	235
85	254


- 1) Contractor pressure = 118 psig
- 2) Contractor saturation temp. = 42 F
- 3) Rater saturation temp. = 40 F
- 4) Difference in saturation temp. = 2 F



Pressure / Temperature Chart

# Item 1.2.12: Review of contractor checklist

- Verify difference between Rater-calculated and contractor-reported target temp.: Subcooling is  $\leq 3^{\circ}\text{F}$  or Superheat is  $\leq 5^{\circ}\text{F}$ .



## Item 1.3: Static pressure test




- Measure the static pressure of the supply duct system and the return duct system.
- Use the same test hole locations as the contractor.
- Watch the video of how the contractor does this at:  
[http://www.energystar.gov/index.cfm?c=bldrs\\_lenders\\_raters.nh\\_videos](http://www.energystar.gov/index.cfm?c=bldrs_lenders_raters.nh_videos)





# Item 1.4: Register airflow



Sample Balancing Report


Room	Register	Design Airflow	Actual Airflow	Difference
Hallway	1	40	29	11
Hallway	2	40	52	12
Room A	1	80	76	4
Room A	2	80	66	14
Room B	1	80	95	15



# Item 1.4: Register airflow



- Methodologies for measuring airflow at registers:
  - ACCA QI 5 standard includes protocols for HVAC contractors (Section 5.2)
  - HERS Mortgage Industry National HERS Standards includes methods for Home Energy Raters to use (Section 804.2)



# Item 1.4: Register airflow



r.  
r, or,  
n

## Section 2: Duct quality installation

---



- Items 2.1 through 2.4 focus on installation defects like kinks, bends, compression, and excessive ductwork.

## Section 2: Duct quality installation



### Compression



# Section 2: Duct quality installation




## Bends & Kinks



## Section 2: Duct quality installation



Sharp Bend





## Item 4.1: Total duct leakage

---

- Total duct leakage  $\leq 8$  CFM per 100 square feet of conditioned floor area.
- More challenging to meet with building cavities as ducts.
- Testing must occur at “final” – when all components of the system are installed including the air handler, ductwork, duct boots and register grills atop the finished surfaces.
- An additional test at “rough-in” is helpful to many partners, but is not mandatory.
- Partners are permitted to seal both the face and the perimeter of the register when testing.
- Sealing between duct boot & subsurface is critical.



## Item 4.1: Total duct leakage

- Using a building cavity for the return system makes it very challenging to meet the leakage limit.



## Item 4.1: Total duct leakage



- If the gap is big enough that your finger can fit in...
- There might be an air leak.



# Summary

---



- A complete thermal enclosure system is the first step towards a complete HVAC system.
- HVAC design typically follows a three-step process:
  1. Calculate the loads.
  2. Select equipment to meet those loads.
  3. Design a duct system from the equipment to the rooms, and back, to offset those loads.
- Provided an overview and reviewed key details of Sections 1 through 4 of the HVAC System QI Rater Checklist.
- These features help improve the efficiency and comfort of every certified home.



# ENERGY STAR Certified Homes

---

## Web:

Main: [www.energystar.gov/newhomespartners](http://www.energystar.gov/newhomespartners)  
Technical: [www.energystar.gov/newhomesguidelines](http://www.energystar.gov/newhomesguidelines)  
Training: [www.energystar.gov/newhomestraining](http://www.energystar.gov/newhomestraining)  
HVAC: [www.energystar.gov/newhomesHVAC](http://www.energystar.gov/newhomesHVAC)

## Email:

[energystarhomes@energystar.gov](mailto:energystarhomes@energystar.gov)

## Social Media:



@energystarhomes



[facebook.com/energystar](https://facebook.com/energystar)

## Contacts:

### Dean Gamble

US EPA  
Technical Manager,  
ENERGY STAR Certified Homes  
[gamble.dean@epa.gov](mailto:gamble.dean@epa.gov)

### Rick Gazica

ICF International  
Account Manager,  
National Builder Support  
ENERGY STAR Certified Homes  
[egazica@icfi.com](mailto:egazica@icfi.com)