Designing And Building Our Net-Zero Home: Knowledge Gained And Lessons Learned

Presenters: Matthew Vande and Amy Musser



DESIGN



Topics to be discussed

General Information About Our House
Construction / Design Strategies
How We Got To Net-Zero
Successes... And Some Lessons Learned
Q&A





- Location: Asheville, NC
- Climate Zone 4
- 1900 SF home / 1200 SF office
- 3 bed / 2.5 bath
- Passive / active solar
- All-electric home

- HERS Index w/o solar = 44
- Final HERS Index = 12
- Certifications: Energy Star, LEED for Homes (Platinum), EPA Indoor AirPlus, NC HealthyBuilt Homes (Platinum)















Ξ

H

Ï

Ξ

al ee

H



ΠH

ΠĨ

Ħ

Strategies – Passive / Active Solar



- 418 SF glazing on south (70%) 17.7% WWA
- 182 SF glazing on other sides (30%)
 17.5% WFA



Strategies – Passive Solar



- Double-pane (triplepane problematic for high SHGC)
- North, east, and west windows: U-value = 0.33 / SHGC = 0.23
- South windows:
 U-value = 0.36 /
 SHGC = 0.53
- Properly sized overhangs over all south windows

Ë

Strategies – Foundation Walls

- Pre-Insulated (R12.5) Panelized Foundation with R19 FG (R31.5 total)
- Foundation was set in 3 hours
- Very easy to finish out
- Office is in walk-out basement (CHEAP SQUARE FOOTAGE!)



Strategies – Basement Slab



- Integral color
- 4" 2500 psi normal weight concrete over 2" rigid insulation (R10)
- 30% fly ash content
- Granite aggregate
- Ground and polished

Ë

Strategies – Main Floor Slab

- 3" 4000 psi normal weight concrete over ³/₄" rigid insulation (R3) over trusses
- 30% fly ash content
- Local river stone aggregate
- Semi-translucent surface-applied color
- Ground and polished



Strategies – HVAC

- 3-ton geothermal heat pump w/ 2 zones
- Able to switch between forced air and hot water (radiant)
- 2 vertical wells, each at 250 feet deep



Strategies – HVAC

- Required ventilation (ASHRAE 62.2) = 62 cfm
- Fresh air ventilation energy recovery ventilator (ERV)
- Low energy usage approx. 40 watts





Strategies – Radiant Heat

- Comfort issue, not an energy saver.
- Radiant heat powered by geothermal heat pump (low temp)
- Lower and main floors are radiant slab
- Upper floor has radiant wall —



Strategies – Radiant Heat



Strategies – SIP Walls / Roof

 Urethane Structural Insulated Panels (SIP) panels • 4.5" walls (R24) • 6.5" roof (R38)



Strategies – Rim Joist





Strategies – Rafter Tails



- Rafters that penetrate through exterior walls tend to have a devastating effect on envelope leakage
- Rafter tails are false separate piece lagged to SIP roof from above
- Exterior sheathing of SIP is continuous

Ë

Ε

() III () IIII () III () IIII () III () IIII () III () IIII ()

Goal: To build for same amount as everyone else...



Getting to Net-Zero



 Electrical Circuit Monitoring • First 12 months: • 5843 kWh used • 6147 kWh generated



Getting To Net-Zero

Water Heater

- Electronic timer on water heater to force solar panels to do most of work
- Electric back-up only allowed to heat from 4:00 to 6:00 (cheaper power) if tank temperature is low
- Most of our hot water use is early morning

Ϊ



Π

ΪË

TT

Getting To Net-Zero



Office Electrical Use

- Before we installed the eMonitor, computers in office left on 24/7
- After installation, turned off most computers at end of work day (60% reduction in office power usage)
- Monthly savings \$20 to \$25



Getting To Net-Zero

Clothes Dryer

- Fairly significant power user when running
- We only use it at night and on weekends (cheaper power)
- If the sun is out, we dry our clothes outside on a clothes line instead.

Ϊ

This Month	To date: \$1	\$2 (<\$1/day)
Last Month	To-same day: \$1	\$2 (<\$1/day)

Energy Consumption Per Load

Projected Costs vs Previous Period

	Number of Loads	Avg Cost per Load	Avg Energy per Load (kWh)	Avg Duration per Load (min
Yesterday	0	0	0	0
Last 7 Days	3	0.03	2.56	35
Last 30 Days	15	0.08	1.8	27



Ϊ

L.B.

Dryer, Hourly View for the Past Month

Π

Getting to Net-Zero



B

ΕÐ

Ϊ

Heat Pump

H

ΪË

PL III

- In cold weather, our biggest energy user (by a lot!)
- Winter thermostat currently set at 71 degrees
- Could likely eliminate a lot of heat pump activity if we lowered it to 68 degrees...

E

Lessons Learned – Mech. Room



- NOT BIG ENOUGH!
- Electrical panel and PV inverter had to be relocated to workshop
- ERV is not ideally located
- Radiant manifold for main floor tubing is above ceiling in office
- A/V controls are in adjacent closet

) mini mini

Ê

Lessons Learned – Ghetto Wine Cellar





- Intentionally left area in basement under stairs unconditioned / removed foundation insulation
- Relative humidity too high (typically 73% 80% RH)
- Temperature swing too large (59° winter -70° summer)
- Ideal wine storage: 50-70% RH / 55°-57°F
- Removed too much insulation at top of foundation wall above grade (condensation in Winter / overheating in Summer)

Ϊ

• Air leakage from rest of house

Lessons Learned – Toilets



- Don't be swayed by aesthetics only...
- Dual-flush 1.6 / 0.8 gpf
- MaP rating = 600g
- Doesn't flush worth a s***!
- 1.6 gpf x 2 flushes = 3.2 gal.
- <u>http://www.map-testing.com</u>
- ALWAYS get one that can flush >1000g
- Plenty of 1.28 gpf options

Ē

<u>Annin Indu</u>

Lessons Learned – Box Elder Beetles

- Property had several box elder trees (we still have 1)
- Spring and Fall breeding seasons
- They LOVE south-facing masonry walls to lay eggs
- Totally harmless don't have interest in coming inside
- Spray with a mix of dish soap and water to kill them





Lessons Learned – Effects Of A Bad Economy

- Built in worst part of the recession
- Bank loan was problematic needed HELOC to pay contractor for materials (bank took too long)
- We thought subcontractor labor would be cheaper, building materials would be plentiful and immediately available
- Subcontractors were actually running skeleton crews (and often letting most experienced / expensive employees go)
- Building supply companies were extremely under-stocked
- To build with any quality, it was going to be both slow *and* expensive.





Lessons Learned – Radiant Heat

- Consciously did it knowing it was not an energy saver
- Coordination of tubing with floor penetrations/saw cuts
- Doesn't run very often due to thermal mass (in Winter, if sunny the day before, usually comes on around 3:00 AM)
- <u>COST</u> (of installing tubing storage tank, and specialized equipment) \$11000 +/-



Lessons Learned – SIP's

- Coordination of window / door openings
- Electrical whining, schedule
- Structural beam pockets
- Builder's learning curve

ΪÏ

B

• <u>COST</u>

Ξ



Ϊ

T

Ξ

H

Lessons Learned – SIP's

- Frame walls with 2x4 framing at 16" on center with R15 fiberglass batts in cavity / R10 continuous exterior insulation board AND change roof to TJI rafters at 16" on center with 8" open cell foam (R30):
- Additional cost of SIP roofs (R38) and walls (R24):
- Annual energy savings to make change to SIP's:

• Rate of payback:

Ë

\$18,000

\$12,000

\$5

ΪË

2400 years

Lessons Learned – ERV

- In a tight house in Asheville, controlling humidity is an issue 12 months out of the year
- Prone to window condensation in winter
- Better choice probably would have been an HRV (more efficient in winter/less in summer/overall neutral)
- Our AC would handle the latent load in summer.
- HRV would also have been slightly cheaper - \$150



Temperature / humidity in kitchen at 3:00 PM on February 14, 2013



Lessons Learned – Fireplace

- EPA-certified fireplace insert
- Wood burning 70% efficient
- Did we need it? Original thought was backup heat in case of power outage.
- Works great, but we have had one small fire so far (2 winters in house) – mostly out of guilt...
- So efficient, it tends to overheat the living area
- Cost: \$5000



Ξ

Things we could have cost-optimized:

 Eliminate radiant heat (forced air only) 	(\$11,000)
 Eliminate SIPS (use continuous exterior rigid ins.) 	(\$12,000)
 HRV in lieu of ERV 	(\$150)
 Eliminate fireplace 	(\$5,000)
 Eliminate rainwater harvesting (city water is very cheap in Asheville) 	(\$3,000)
TOTAL	(\$41,150)
 Original cost / SF (including incentives) 	\$156 / SF
 Optimized cost / SF (no change in performance) 	\$143 / SF

H

Ē

Successes – Natural Light



- HUGE impact on mood and productivity
- Has changed our sleeping patterns
- Almost never need lights on during the day, even when cloudy
- Overhangs sized to fully shade windows at noon on Summer solstice
- Sun penetrates full depth of house at noon on Winter solstice

Ē

Successes – Thermal Mass Floors

- Thermal mass floors heat up dramatically on sunny Winter days
- Polished concrete floors are durable, low-VOC, and contain recycled fly ash
- Similar finished cost to high-end hardwood or tile floors



Ê

Successes – Rainwater Harvesting



- 3000-gallon rainwater cistern
- Collects water off 80% of roof area
- Standing seam metal roof reduces contaminants
- Toilets and outside hose bibbs only (non-potable) / independent plumbing lines
- Booster pump in mechanical room for easy maintenance
- Reduced city water usage by 50%



Successes – Financial Incentives

 Geothermal (30% Federal / 35% State) 	\$17,150
 Geothermal + Energy Star (Utility Rebate) \$1,000
 Solar Thermal (30% Federal / 35% State) 	\$2,535
 Solar Thermal (Utility Rebate) 	\$1,000
 Photovoltaic (30% Federal / 35% State) 	\$19,400
 Photovoltaic (Utility Rebate) 	\$5,150
 EPAct \$2000 Federal Builder Tax Credit 	\$2,000
 Passive Solar Tax Credits (State) 	\$3,500
 Local Permit Fee Rebates 	<u>\$200</u>
total incentives	\$51,935
reduction in cost / SF	(\$16.72) / SF
estimated rate of payback	7 to 10 years



Any Questions?

S Progress Energy	Customer Bill page 1 of 1		
	Account number		
0050931 01 SP 0.450 051	Total due	\$1.19	
	Current charges past due after Jul 30		
AMY B MUSSER 26 CRABAPPLE LN	Thank you for your payment Jun 13	\$1.83	
ASHEVILLE NC 28804-1733		4 - Jul 3	
		6, 2012	
kWh Usage History 1,300 975 650	Usage Meter number Readings: Jul 3 Jun 4 kWh usage	RC9717 4708 4434 274	
325 0 Jul Sep Nov Jan Mar May Jul	Days in period 29 Average kWh per of Total Peak Registration	lay 9	
our sep nov van mar may var	On-peak KW Jul 2 at 8:59 pm	2.21	
	Off-peak KW	6.14	
		The shift of the	

R. H

ER

₩